

NOTES

1. All drawings to be read in conjunction with Structural Engineer's details & any relevant sub-contractor's details, works to comply with current Building Regulations, British Standards & Codes of Practice.

2. The Main Contractor & Sub-Contractor where applicable be responsible for checking all dimensions on site & report any discrepancies to all relevant consultants.

3. The contractor must familiarize himself with the site and measure all areas affecting his work. All dimensions must be verified on site prior to manufacture of any girder or web or of site.

4. All works to be carried out by approved installation contractors, and to manufacturers' recommendations.

5. All dimensions to be in millimeters.

6. Contractor to ensure that all work meets the requirements of the EHO, Building Control, Fire Authority and all other statutory bodies.

7. All shop-fit decoration to achieve Class "D" surface appearance in accordance with BS476, Part 7, 1973 or 1982.

ft. All stained timber areas to be treated with Thermoguard or similar to achieve Class "C" surface spread of flame. All pointed timber areas to be treated with Thermoguard Timbercoat or similar to achieve Class "C" surface spread of flame.

2, Where MCF is specified this is to be Zero or Low Formaldehyde type MCF made to British Standards.

10). The contractor is to ensure that all walls to be decorated prepared prior to decoration and all surfaces smooth level joint free.

All applied coatings are to be water based to large wall area. Contractor to allow for one mil coat and two top coats in a wall and timbers.

All new Strider to be pressure impregnated with preservative prior to delivery to site. Where subsequent cutting & bonding necessary all exposed faces to be coated with Duxone.

REVISIONS

[illegible]

**KEANE. THINKING
LIFESTYLE
DESIGN**

BOW STREET, BIRMINGHAM B1 1DW
Telephone 0121 666 6607

CLIENT

KIKI CONCEPTS LTD.

PROJE

100

1

1

PROPOSED GA PLAN

SCALE

1:100 @ A1

DATE _____

29.01.16

DO NOT

12051

9

to display in the page

Figure 4

Alfred De Santis is a writer
living in the city of New York.

to be read in conjunction with

1
