


**KEY TO PARTITION SETTING OUT DRAWING**

Some symbols shown may not appear in drawing, and may not be to scale. Drawing must be printed in colour.

**Existing fit-out**



**New partitioning & glazing types**

**New straight partition built from raised access floor to underside of suspended ceiling**  
 to include two layers of standard plasterboard either side of metal studs. To be tape and jointed & decorated. 100mm MDF skirting.

**New straight partition built from slab to slab, 110mm thick with 2no. layers of 15mm Gyproc Soundbloc board each side of 70mm Gyplam 'C' studs 600mm centres & built in accordance with the British Gypsum instructions and Standards. Cavity to be filled with isover acoustic partition roll (APR 1200) to achieve 49 Db sound insulation. A single layer of steel mesh is to be provided either side between the plasterboard for security purposes. Partition construction is to achieve a minimum 60 minute fire resistance. Head & foot of partition to be sealed with an intumescent mastic, including to wall surfaces where these adjoin existing wall/columns, to ensure sufficient fire separation and to provide a sharp finish**

**New straight half-height partition built from raised access floor to 1200mm FFL to include two layers of standard plasterboard either side of metal studs. To be tape and jointed & decorated. 100mm MDF skirting.**

**New boxing in/wall lining/service void built full height from raised access floor to underside of suspended ceiling, to include two layers of standard plasterboard one side of metal studs. To be tape and jointed & decorated. 100mm MDF skirting.**

**New single glazed silicone jointed glazing. New 12mm standard glass, 2700mm FFL silicone jointed & to sit within aluminium track.**

**New single glazed silicone jointed glazing. New 12.8mm acoustic glass, 2700mm FFL silicone jointed & to sit within aluminium track.**

**PLY** Ply partition strengthening to allow fixing of heavier items

**DL** Existing core wall to be dry lined

**BP** Doors and glazing to have partition bulkhead above the partition line built to underside of suspended ceiling

**New doors (refer to door schedule for specification)**



**VP** = Vision Panel  
**FD30** = 30 minute fire rating  
**FD60** = 60 minute fire rating  
**FD60S** = 60 minute fire rating with smoke seal

INFOPRO - BP075 - 22/01/2024  
 PARTITION TYPE DETAILS - CONTRACT ISSUE - REV C  
 5TH FLOOR & 133 HOUNDSDITCH LONDON  
 SCALE 1:100 @ A1

