



SOUTH FACING ELEVATION
Scale 1:50

NORTH FACING ELEVATION
Scale 1:50

ELEVATION KEY:

	INDICATES AREAS OF BARBICAN TERRACE RAILING.		INDICATES AREAS OF BRICKWORK.
	INDICATES AREAS OF CLEAR GLAZING.		INDICATES AREAS OF INSULATED RENDER.
	INDICATES AREAS OF TOUGHENED SAFETY GLASS.		INDICATES AREAS OF PARAPET CAPPING.
	INDICATES AREAS OF BALUSTRADE.		INDICATES WINDOW/DOOR REFERENCES.

MATERIALS KEY:

A	INDICATES AREAS OF FACING BRICKWORK IN STRETCHER BOND. PATTERN - COLOUR: ISTOCK ATLAS SMOOTH BLUE.	D	BARBICAN TERRACE RAILING. COLOUR: RAL 7000. NO OPENING GREATER THAN 100mm.	G	CLEAR TOUGHENED GLAZED BALUSTRADE. 1100mm HIGH FROM FFL.	K	ALUMINIUM PARAPET CAPPING. COLOUR: RAL 7000.
B	FULL-HEIGHT PPC GALVANISED STEEL/ ALUMINUM GATES TO MATCH BALCONIES	E	PRESSED ALUMINIUM FINISH. COLOUR: RAL 7000	H	ALUMINIUM WINDOWS/DOORS. COLOUR: RAL 7000.	L	FROSTED TOUGHENED GLAZED BALUSTRADE. 1800mm HIGH FROM FFL.
C	INSULATED RENDER SYSTEM BY STO. COLOUR: WHITE.	F	RAINSCREEN CLADDING BY OTHERS	J	ALUMINIUM/STEEL SQUARE DOWNPIPES AND HOPPERS. COLOUR: RAL 7000.		

01	Building Regulations Issue	24.06.21
00	Initial Draft Issue	22.02.21
Rev.	Description	Date