

# LSH-S-BE

## LIFT SYSTEM HEAVY SWIVEL & BOX ENCLOSURE



future automation

### INTEGRATION CONSIDERATIONS



#### High Risk - Crushing

Crush hazard between the top panel and the cabinet top as the lift closes.



#### Mitigation

Install a pressure switch below the top panel to detect any obstructions. A pressure switch can be installed between two timber panels to allow the vertical movement required for switching.



#### Low Risk - Crushing

Crush hazard at the cabinet aperture when mechanism is opening.



#### Mitigation

Keep the gaps between the cabinet aperture and the moving panels to a minimum (no smaller than 3mm [1/8"]) to reduce the risk of obstruction. Install a pressure switch below the cabinet top to detect any obstructions.



#### High Risk - Crushing

Crush hazard below the mechanism when mechanism is closing.




#### Mitigation

Ensure area below the mechanism is kept clear at all times when the mechanism is being used. If installing or maintaining the mechanism do so with the mechanism turned off.

#### General Mitigations:

- Implement a hold to run/dead man switch operation.
- Control methods should be located within direct line of site of the mechanism.
- Implement password or key switch protected operation.



#### Low Risk - Falling Objects

Falling object hazard if objects are left on top of the top panel.



#### Mitigation

See general mitigations.



#### Low Risk - Impact

Impact hazard around mechanism when swivelling.



#### Mitigation

Set swivel limits to prevent impact with surrounding objects/ structures. Ensure sufficient space is left between the screen and any obstructions.



#### Low Risk - Crushing

Cables could be snagged if not properly managed through and around the mechanism, causing damage to the mechanism and electronics.



#### Mitigation

Ensure sufficient cable slack is allowed around movement joints to prevent stretching and/ or damage to the cables and/ or mechanism.